

Additional notes as requested by Buckinghamshire Highways

- Any covers likely to be overrun must be D400 Heavy Duty specification.
- All works must be inspected in accordance with the Council's 'pre-commencement ticksheet' available upon request from the Council's Highways Development Management Team.
- All highway verges effected by the works must be top soiled and seeded prior to the provisional certificate being issued.
- All existing highway reinstatements must be one full lane width minimum i.e to the centreline.
- Any tie-in areas must be discussed and agreed with the Transport Inspector onsite.
- The contractor must present NRSWA accreditation cards upon Inspector's request onsite.
- All lining within the extents of the scheme to be refreshed.

Sign Schedule (dims in mm)		
Sign Ref	TSRDG Ref	Size (mm)
S1	883	"x" height to be 75 mm

Sign to be mounted on 760 posts and mounted in accordance with Buckinghamshire Highways standard detail drawing PGS-SD-1200-001



Diag. no. 883
Exact location of sign to be determined on site following stats check.

Cont'd on below

Cont'd on Drawing 12-005-502

Cont'd on Drawing 12-005-502

PROPOSED BUILD OUT WITH IMPRINT PAVING (TRAFFIC CALMING FEATURE 2)

PROPOSED GATEWAY FEATURE WITH NEW CHICANE FEATURE (TRAFFIC CALMING FEATURE 1)

ISSUED FOR CONSTRUCTION
TECHNICALLY APPROVED BY ADOPTING AUTHORITY

Sign Ref	TSRDG Ref	Size (mm)	Supplementary Plate
S2	879	450 X 450	
S3 *	615	600 wide	Give way to oncoming vehicles
S4	811 A	600 wide	Priority over oncoming vehicles
S5	811 A	600 wide	Priority over oncoming vehicles
S6	811 A	600 wide	Priority over oncoming vehicles
S7 *	615	600 wide	Give way to oncoming vehicles
S8	811 A	600 wide	Priority over oncoming vehicles
S9 *	615	600 wide	Give way to oncoming vehicles

All signs to be mounted on 760 posts and fitted into NAL sockets and mounted in accordance with Buckinghamshire Highways standard detail drawing PGS-SD-1200-001
Signs shown (*) are to be externally lit using solar panels mounted to top of sign posts

Line Type Schedule (dims in mm)					
Diag.	Width	Colour	Line	Space	Line
1003 A	200	White	600	300	600
1004	100	White	4000	2000	4000
1009 A	100	White	600	300	600
1010	100	White	1000	1000	1000
1028.4	100	White	600	600	600
1049 B	200	White	Continuous		
1023 A		White	3750 long		
Bus Cage (1025.1)					
1049 B	200	Yellow	15000 long		
1010	100	Yellow	1000	1000	1000

- NOTES**
- This drawing is to be read in conjunction with the relevant specification and the following drawings:- 12-005-502 to 12-005-511 - General Arrangement Layouts.
 - All materials and workmanship shall comply fully with the Manual of Contract Documents for Highways Works, Specification for Highways Works Volume 1 and the Buckinghamshire County Council Specification for Road Construction and Standard Details.
 - Refer to drawings 12-005-512 to 12-005-522 inclusive for Site Clearance Plans.
 - Refer to drawings 12-005-523 to 12-005-533 inclusive for Surface Finishes Plans.
 - Refer to drawings 12-005-534 to 12-005-544 for the Existing Services Plans.
 - Do NOT scale from this drawing. Work from figured dimensions and Setting Out information ONLY.
 - Any covers likely to be overrun must be D400 Heavy Duty specification.
 - All works must be inspected in accordance with the Council's 'pre-commencement ticksheet' available upon request from the Council's Highways Development Management Team.
 - All highway verges effected by the works must be top soiled and seeded prior to the provisional certificate being issued.
 - All existing highway reinstatements must be one full lane width minimum i.e to the centreline.
 - Any tie-in areas must be discussed and agreed with the Transport Inspector onsite.
 - The contractor must present NRSWA accreditation cards upon Inspector's request onsite.
 - All lining within the extents of the scheme to be refreshed.
 - Any covers likely to be overrun must be D400 Heavy Duty specification.
 - All works must be inspected in accordance with the Council's 'pre-commencement ticksheet' available upon request from the Council's Highways Development Management Team.
 - All highway verges effected by the works must be top soiled and seeded prior to the provisional certificate being issued.
 - All existing highway reinstatements must be one full lane width minimum i.e to the centreline.
 - Any tie-in areas must be discussed and agreed with the Transport Inspector onsite.
 - The contractor must present NRSWA accreditation cards upon Inspector's request onsite.
 - All lining within the extents of the scheme to be refreshed.

- LEGEND**
- Proposed cycle lane
 - Cycle lane separator NCDL Lite by Rosehill Highways (or similar approved), Rosehill drawing no. RHP 0049. Separators marked "*" to be fitted with bollard as per drawing. Separators to be placed as shown with minimum 1.0m gap.

Rev	Amendments	Drn	Chk	App	Date
K	Amended following discussions with BC highways	EV	GG	GC	Mar 25
J	Amended as ballooned	EV	GG	GC	Mar 25
H	Amended following discussions with BC highways	EV	GG	GC	Mar 25
G	Amended following discussions with BC highways	EV	GG	GC	Feb 25
F	KEEP CLEAR road markings added as ballooned to double mini-roundabout.	EV	GG	GC	Nov 24
E	Feature 2 amended following comments from BC highways.	EV	GG	GC	Sept 24
D	Issued for Construction - Technically approved	EV	GG	GC	July 24
C	Lining table amended following Technical Comments 3 from BC highways	EV	GG	GC	July 24
B	Amended following Technical Comments 2 from BC highways	EV	GG	GC	July 24
A	Amended following comments from BC highways	EV	GG	GC	May 24



Issued by Park House
 Station Road
 Aylesbury
 Bucks HP20 9HA
 01296 636420
 enquiries@c.a.uk.com
 www.c.a.uk.com

Job Title

**Kingsbrook, Aylesbury
Bierton Traffic Calming Measures**

Drawing Title
**General Arrangement Layout
Sheet 1 of 11**

Client
BDW North Thames Ltd

Scale	Date	Designed
1:250 @ A1	Jan 24	GG

Drawn	Checked	Approved
EV	GW	GAC

Job No	C & A Drawing No	Rev
12-005	12-005-501	K

Client Drawing No
12-005-H6700-D2-501